Publisher homepage: www.universepg.com, eISSN: 2663-7804

Australian Journal of Engineering and Innovative Technology

Journal homepage: www.universepg.com/journal/ajeit

OPEN ACCESS | Research Article

# Operational Monitoring of Attenuation and Optical Power Budget in Fiber-Optic Lines at Power Facilities

**Ilia Strelnikov***

Engineer of the First Category, Service of Corporate and Technological Automated Control Systems, SC Rosseti Tyumen, Tobolsk, Russian Federation

*Correspondence: strelnikov-ia@te.ru (Ilia Strelnikov, Engineer of the First Category, Service of Corporate and Technological Automated Control Systems, SC Rosseti Tyumen, Tobolsk, Russian Federation).

Received Date: 9 July 2026 Accepted Date: 11 August 2026 Published Date: 18 August 2026

**Abstract**

Fiber-optic lines have become the technical base for digital communication at power facilities, where dispatching, control, security, and corporate services depend on stable channels. This article examines attenuation and optical power-budget monitoring as operational tasks that link installation quality, contractor acceptance, scheduled inspections, and equipment lifecycle decisions. The aim is to formulate an analytical framework for routine control of fiber-optic lines under power-sector constraints. The study uses source analysis, comparative review, conceptual synthesis, classification, and analytical generalization. The source base covers ten publications from 2021 to 2025 on smart-grid communications, fiber use in electrical power engineering, OTDR-based diagnostics, online fiber monitoring, and optical performance control. The analytical part defines the place of attenuation measurement and power-budget verification in maintenance practice, clarifies the relationship between offline and online tools, and connects the monitoring discipline to mixed-vendor equipment environments. The proposed logic applies to substations and grid communication nodes without disclosing protected schemes.

**Keywords:** Smart-grid communication, OTDR, Receiver sensitivity, Fault localization, Equipment lifecycle.

## 1. Introduction

Power facilities increasingly rely on communication channels that carry technological and corporate traffic across substations, dispatching points, automated control systems, and security circuits. Earlier configurations based on copper cable and high-frequency communication over power lines covered narrower service needs. Ethernet exchange, remote access, video streams, automated control, and cybersecurity supervision require higher bandwidth and stable channel behavior. For this reason, the transition to fiber-optic communication changes maintenance practices as much as it increases network capacity (Momand *et al*., 2023).

The research aim is to develop an operational approach to attenuation and optical power budget monitoring in fiber-optic lines at power facilities. The first objective is to define the relevance of attenuation and power-budget control during the transition from legacy communication media to fiber-optic channels. The second objective is to classify diagnostic tools and maintenance logic for scheduled and event-driven control of installed fiber links. The third objective is to connect monitoring

practices with equipment selection and software support in mixed-vendor infrastructure environments (Shokralla, 2024).

The novelty of the article lies in the combined treatment of physical-line measurement, power-sector communication reliability, and equipment lifecycle management. The proposed view treats attenuation control and optical power budget verification as ongoing operational disciplines after commissioning. The hypothesis states that stable digital communication at power facilities depends on routine measurement discipline and optical reserve control more than on fiber deployment as a single infrastructure upgrade.

## 2. Methodology

The material comprises publications from 2021-2025, selected through a thematic screening of recent work on power-sector communications, fiber-optic monitoring, and optical-layer diagnostics. The screening excluded general telecom papers that did not address maintenance, monitoring, fault localization, or power infrastructure. The final corpus covers communication requirements for smart grids (Abrahamsen *et al.*, 2021), joint use of fiber optics and broadband over power lines in grid communication architecture (Lazaropoulos & Leligou, 2022), fiber applications in electrical power engineering (Poczekajło *et al.*, 2024), FPMT-based online fiber-line monitoring (Ibrahim *et al.*, 2022, 2023), machine-learning-based anomaly detection in optical fiber monitoring (Abdelli *et al.*, 2022), correlation-aided time-domain reflectometry (Eiselt *et al.*, 2023), long-reach fault-detection logic (Liu *et al.*, 2024), state-of-polarization-based anomaly identification (Malik *et al.*, 2025), and machine-learning-aided optical performance monitoring (Tizikara *et al.*, 2022). Together, these sources connect power-facility communication requirements with physical-link diagnostics and optical-layer observability.

Comparative analysis separated power-sector communication requirements from conventional optical network monitoring tasks. Source analysis supported the selection of concepts related to attenuation, optical budget, and fault localization - conceptual synthesis connected scheduled field measurements with online monitoring models. Classification grouped operational decisions by maintenance purpose. Analytical generalization supported the proposed monitoring logic for power facilities.

## 3. Results

Current smart-grid communication research treats bidirectional, reliable information exchange as a prerequisite for automated power-system operation (Abrahamsen *et al.*, 2021). This point matters for power facilities because communication failures affect remote control, dispatch coordination, visibility into substation status, and interaction between the corporate and technological systems. The operating team needs repeated confirmation that accumulated loss and optical reserve remain compatible with the transceiver pair and the route configuration.

The transition from copper cable and high-frequency power-line communication to fiber optics changes the maintenance object. Legacy channels often led personnel toward electrical continuity, radio-frequency quality, or service availability checks. Fiber-optic channels require a different field routine: connector cleanliness, splice quality, bend control, fiber identification, transmitter output, receiver sensitivity, and route loss. Researchers who study smart-grid communication architecture describe fiber optics and broadband over power lines as complementary technologies across high-voltage, medium-voltage, and low-voltage grid segments (Lazaropoulos & Leligou, 2022). This position fits power-facility practice. Fiber can serve as a backbone for traffic aggregation, while other media remain suitable for particular routes and access conditions.

Recent work on fiber-optic technologies in electrical power engineering broadens the meaning of fiber infrastructure. Researchers describe applications related to communication, power-line integration, sensing, fault detection, overheating control, and power delivery to devices (Poczekajło *et al.*, 2024). For the present topic, this source has direct operational value. A fiber route at a power facility often belongs to a technical environment where communication, future diagnostics, and route documentation intersect. Attenuation monitoring and power-budget verification protect the current channel and preserve technical readiness for later services where the design permits such use.

The optical power budget links equipment selection to cable-route conditions. In operational terms, it reflects the allowed loss between the transmitter output and the receiver sensitivity, after route losses and the reserve margin. The total loss is due to fiber attenuation, splices, connectors, patching, passive elements, bending, and defects introduced during installation or maintenance. A measurement of received power alone can hide the location and origin of degradation. An OTDR trace without power-budget interpretation can describe events but leave the operator without a serviceability conclusion for the installed transceivers. Scheduled maintenance needs both readings.

FPMT-based online monitoring research proposes remote detection, localization, and estimation of fiber faults without traffic interruption (Ibrahim *et al.*, 2022). The exact architecture belongs to optical communication networks, but its maintenance logic is well-suited to power facilities. Operators need to distinguish a break from gradual degradation. A break requires emergency localization. Gradual growth of loss, connector reflection, or bending calls for planned correction before the receiver margin disappears. In substation communication work, this distinction reduces avoidable emergency repairs and supports contractor feedback after installation defects appear.

A later FPMT study integrated an EDFA optical amplifier and focused on remote real-time monitoring of optical-layer performance (Ibrahim *et al.*, 2023). Power utilities cannot transfer every such architecture to distribution-level links because route length, topology, access restrictions, and equipment class differ across facilities. The transferable conclusion concerns monitoring depth. Acceptance tests and scheduled measurements form the base. Online monitoring is reasonable for links where communication failures could cause operational delays or require expensive field visits.

Machine-learning-based optical fiber monitoring shifts attention from isolated readings to trace patterns and event classification (Abdelli *et al.*, 2022). This direction matters because OTDR interpretation often depends on experience. Connector reflections, bends, splice defects, partial mechanical disturbance, and fiber cuts can produce trace changes that require disciplined comparison with earlier records. Automated classification can help staff screen suspicious traces and prioritize work. Operators still need raw traces, route documentation, and field verification before repair decisions.

Correlation-aided time-domain reflectometry adds another diagnostic route. Researchers report monitoring of optical transmission paths through correlation-based OTDR techniques with direct and coherent detection (Eiselt *et al.*, 2023). This line of work extends monitoring beyond conventional pulse OTDR and supports sensitivity to propagation delay and dynamic effects near the fiber. For power facilities, the value lies in selection. A short distribution substation link and a backbone transport route require different diagnostic depths. The maintenance team should match tool complexity to channel consequence, route length, and access difficulty.

Fault-detection research for long-reach mode-division multiplexing links shows that localization quality is linked to fault type, spatial modes, crosstalk, and mode coupling (Liu *et al.*, 2024). Conventional utility links often use other optical configurations, but the methodological lesson remains useful. Measurement results depend on the method's assumptions and the link's physical structure. A trace should be read in conjunction with the cable type, route documentation, connector scheme, passive elements, and test wavelength. Without this information, staff can confuse a measurement artifact with a line defect.

Several recent monitoring directions point toward layered control. FPMT studies focus on online detection of soft and hard failures (Ibrahim *et al.*, 2022, 2023). Machine learning and state-of-the-art polarization approaches classify harmful events, mechanical disturbances, and suspected tapping scenarios (Abdelli *et al.*, 2022; Malik *et al.*, 2025). Correlation-aided reflectometry strengthens sensitivity to path changes (Eiselt *et al.*, 2023). Together, these approaches support a practical arrangement for power facilities: basic scheduled measurement confirms line condition, reflectometry explains the distribution of events, and online or intelligent tools support links with higher operational consequence. Machine-learning-aided optical performance monitoring literature connects optical parameters with

performance degradation recognition and network control tasks (Tizikara *et al.*, 2022). For power facilities, operators need the part that improves maintainability, record quality, and early detection of reserve loss. **Fig. 1** gives a generalized sequence for attenuation and optical power budget monitoring without object names, route maps, telemetry, or internal thresholds.




**Fig. 1:** Operational sequence for attenuation and optical power-budget monitoring at power facilities, adapted from optical performance monitoring concepts in (Ibrahim *et al.*, 2022; Tizikara *et al.*, 2022).

The equipment and software layer adds a separate maintenance problem. Smart-grid communication research emphasizes that different grid environments require distinct communication architectures (Abrahamsen *et al.*, 2021), and power-grid communication architecture studies describe integrated technologies spanning voltage levels (Lazaropoulos & Leligou, 2022). Optical monitoring studies add a diagnostic requirement: instruments, transceivers, management software, and monitoring platforms should produce records that staff can interpret and compare over time (Ibrahim *et al.*, 2022, 2023; Tizikara *et al.*, 2022). Vendor replacement affects more than procurement. It changes training, interface logic, alarm interpretation, spare-part

planning, and comparability of measurements made before and after the transition.

Attenuation and optical power budget should function as controlled operational states across design, installation, acceptance, scheduled inspection, and repair. The practical contribution of this view lies in its connection between physical measurement and power-sector operating discipline. Fiber-optic channels increase bandwidth and reduce exposure to electromagnetic interference, while communication reliability still depends on the staff's ability to detect optical degradation before the receiver threshold becomes critical.

## 4. Discussion

Operational monitoring of fiber-optic lines at power facilities should begin at acceptance. The operating team needs a baseline record of the link as built: route identity, fiber number, patching points, transceiver pair, wavelength, insertion-loss value, received optical power, OTDR trace, and known passive events. This record serves as a reference during later inspections and helps resolve contractor disputes when degradation occurs after installation or repair. The monitoring model separates three decisions. The first decision concerns fitness for operation after installation or repair. The second concerns degradation during scheduled inspection. The third concerns emergency localization after service interruption. These decisions use partly overlapping instruments, but they answer different questions. Acceptance checks optical reserve against the installed route. Scheduled inspection asks whether the line has moved away from its baseline. Emergency diagnostics identifies the repair zone and the order of restoration work.

A practical procedure starts with documentation. Unlabelled fibers and inconsistent patch records create diagnostic delays before any instrument enters the cabinet. Cleaning and visual inspection of accessible connectors should precede loss interpretation. Insertion-loss measurement and optical power readings then confirm the channel reserve under operating conditions. OTDR measurements provide a spatial picture of loss and reflection events. After these steps, maintenance personnel can keep the line in service, plan connector work, require splice correction, or open a repair task.

**Table 1** compares operational situations that arise during acceptance and scheduled inspection. The table links observed fiber-line conditions with maintenance decisions without using numerical thresholds. Local thresholds belong in equipment specifications, internal instructions, and project documentation.

**Table 1:** Operational decision matrix for scheduled inspection of fiber-optic lines at power facilities.

| Observed condition | Operational meaning | Preferred action | Record to preserve |
|---|---|---|---|
| Stable received power and a stable trace pattern | The line keeps its baseline condition | Keep the planned inspection interval | Measurement date, instrument, wavelength, trace file |
| Increased insertion loss without service interruption | The link consumes optical reserve before users notice a disruption | Inspect connectors, patch cords, and recent work zones | Earlier and current readings, corrective action |
| New reflective event on the trace | A connector, mechanical disturbance, or joining defect may have appeared | Localize the event and verify accessible connection points | Trace comparison and route reference |
| Sudden loss of received power | A hard failure or major degradation has entered operation | Start emergency localization and use the reserve route where available | Detection time, affected service, repair record |
| Divergent readings across instruments | Measurement comparability has become uncertain | Check calibration status, launch conditions, and test procedure | Instrument model, settings, operator note |

The matrix gives maintenance staff a route from observation to action. Its value lies in decision discipline. Power facilities often have limited windows for communication work, so staff should avoid urgent repairs when the service is stable and avoid waiting when gradual reserve loss threatens future availability. Classification reduces both errors.

Equipment choice requires the same discipline. Replacing familiar platforms with alternative equipment and software changes how technicians receive alarms, configure interfaces, store traces, and compare records across years. A low purchase price loses value when software behaves unpredictably, hides raw measurement data, or forces manual record conversion. A simpler instrument or management system can better serve the operating team when it produces stable readings, exports standard files, and aligns with internal checklists.

**Table 2** presents a selection logic for mixed-vendor fiber-optic monitoring environments. The table compares practical criteria used during operational adoption of equipment and software. It avoids vendor ranking and focuses on maintainability, because protected infrastructure should avoid dependence on undocumented knowledge held by a single contractor or individual specialist.

**Table 2:** Equipment and software selection logic for mixed-vendor fiber-optic monitoring.

| Selection criterion | Operational interpretation | Preferred practical requirement |
|---|---|---|
| Usability | Staff perform routine measurement without procedural ambiguity | Clear interface, repeatable workflow, accessible export |
| Interoperability | The device works with existing transceivers, patching, and documentation practices | Standard connectors, common wavelengths, and trace formats suitable for archiving |
| Software stability | Measurement records and alarms keep consistent behavior across updates | Predictable versions, controlled updates, and local backup of records |
| Training load | Vendor transition preserves maintenance readiness | Short instruction cycle and compatibility with internal checklists |
| Service support | Repair and calibration delays affect communication reliability | Available support channel, calibration documentation, and spare accessory supply |
| Lifecycle cost | The purchase price covers only part of the operating burden | Reasonable ownership cost, available consumables, durable accessories |

The monitoring environment should preserve comparability over time. A utility can change vendors, instruments, and software while maintaining continuity in measurement principles, trace storage, connector handling, and staff training. Without this continuity, staff risk confusing true line degradation with a change in measurement procedure.

The implementation model assigns responsibilities across the lifecycle. During design, engineers define expected optical reserve and select equipment that tolerates projected route losses. During installation, contractors document splices, connectors, patching, and fiber identification. During acceptance, the operator verifies insertion loss, received power, and OTDR trace against the design record. During operation, scheduled measurements compare the current state with the baseline. During repair, staff restore the physical line and update the documentary chain.

The model has limits. It cannot replace internal standards, and it excludes protected topologies or operating figures. It requires careful routine work. An accurate trace loses operational value when staff store it without route identification. A connector defect can look like a line problem when personnel skip cleaning before measurement. The procedure depends on small habits: marking fibers, controlling patch cords, recording instrument settings, saving

raw traces, and checking power after any physical intervention.

The transition from copper or high-frequency communication to optical Ethernet channels changes failure patterns. Staff gain bandwidth and reduced exposure to electromagnetic interference. At the same time, optical cleanliness, bending, connector quality, and transceiver compatibility become central maintenance concerns. Personnel who previously worked with electrical continuity and radio-frequency channels need a measurement culture built around optical loss, reserve, and trace comparison.

Critical infrastructure conditions require restrained publication practice. Reports for journals, contractors, or external audits can describe methods, measurement types, decision categories, and general maintenance logic. They should omit object names, route maps, telemetry, raw logs, and internal thresholds. This approach maintains academic value while protecting operational information.

## 5. Conclusion

Fiber-optic migration at power facilities changes the basis of communication reliability. The central operational issue lies in controlled attenuation and optical reserve, because these parameters connect installation quality to transceivers' ability to support service traffic over time. The transition from copper and high-frequency channels to fiber-optic links provides higher bandwidth and reduced exposure to electromagnetic interference. Still, it creates a need for optical-layer documentation and scheduled verification. Routine monitoring should combine insertion-loss measurement, received optical power control, and OTDR-based event interpretation. Online monitoring and intelligent anomaly detection strengthen this logic for higher-consequence links, while planned field measurements remain the base for many distribution-level facilities. Monitoring gains practical value when each reading has a baseline and leads to a defined decision: continued operation, planned correction, contractor claim, or emergency repair. Equipment and software choice influence maintenance quality at the same level as the measuring method. Mixed-vendor environments require attention to usability, interoperability, software stability, staff training, support, and record continuity. The hypothesis stated in the introduction receives confirmation: stable digital communication at power facilities depends on routine measurement discipline and power-budget governance more than on fiber deployment as a one-time infrastructure upgrade.

## 6. Acknowledgment

The author gratefully acknowledges the reviewers and the editorial team for their constructive comments and recommendations, which helped improve the manuscript.

## 7. Conflicts of Interest

This publication is free of any conflict of interest.

## 8. References

Abdelli, K., Cho, J. Y., Azendorf, F., Griesser, H., Tropschug, C., & Pachnicke, S. (2022). Machine-learning-based anomaly detection in optical fiber monitoring. *Journal of Optical Communications and Networking*, **14**(5), 365–375. https://doi.org/10.1364/JOCN.451289

Abrahamsen, F. E., Ai, Y., & Cheffena, M. (2021). Communication technologies for smart grid: A comprehensive survey. *Sensors*, **21**(23), 8087. https://doi.org/10.3390/s21238087

Eiselt, M. H., Azendorf, F., & Lawin, M. (2023). Monitoring of optical networks using correlation - aided time-domain reflectometry with direct and coherent detection. *In 2023 Opto-Electronics and Communications Conference (OECC).* https://doi.org/10.1109/OECC56963.2023.10209673

Ibrahim, A. A., Fouad, M. M., & Hamdi, A. A. (2022). A design fiber performance monitoring tool (FPMT) for online remote fiber line performance detection. *Electro-nics*, **11**(21), 3627. https://doi.org/10.3390/electronics11213627

Ibrahim, A. A., Fouad, M. M., & Hamdi, A. A. (2023). Remote real-time optical layers performance monitoring using a modern FPMT technique integrated with an EDFA optical amplifier. *Electronics*, **12**(3), 601. https://doi.org/10.3390/electronics12030601

Lazaropoulos, A. G., & Leligou, H. C. (2022). Fiber optics and broadband over power lines in smart grid: A communications system architecture for overhead high-voltage, medium-voltage and low-voltage power grids. *Progress in Electromagnetics Research B*, **95**, 185–205. https://doi.org/10.2528/PIERB22062502

Liu, F., Huang, Z., & Gu, T. (2024). Advanced various fault detection scheme for long-reach mode division multiplexing transmission. *Photonics*, **11**(6), 523. https://doi.org/10.3390/photonics11060523

Malik, G., Dipto, I. C., & Curri, V. (2025). Resilient anomaly detection in fiber-optic networks: A machine learning framework for multi-threat identification using state-of-polarization monitoring. *AI*, **6**(7), 131. https://doi.org/10.3390/ai6070131

Momand P, Niazai H, and Safi FRM. (2023). Investigation of the dimensions of making Brillouin laser in optical fiber. *Aust. J. Eng. Innov. Technol.*, **5**(2), 58-62. https://doi.org/10.34104/ajeit.023.058062

Poczekajło, P., Suszyński, R., & Antosz, A. (2024). Review of the usage of fiber optic technologies in electrical power engineering and a development outline in Poland. *Energy Reports*, **11**, 5227–5234. https://doi.org/10.1016/j.egyr.2024.04.068

Shokralla EA. (2024). Dielectric relaxation and thermal stability of epoxy/polyurethane-carbon nanofiber composites, *Int. J. Mat. Math. Sci.*, **6**(3), 38-47. https://doi.org/10.34104/ijmms.024.038047

Tizikara, D. K., Serugunda, J., & Katumba, A. (2022). Machine learning-aided optical performance monitoring techniques: A review. *Frontiers in Communications and Networks*, **2**, 756513. https://doi.org/10.3389/frcmn.2021.756513

Citation: Strelnikov I. (2026). Operational monitoring of attenuation and optical power budget in fiber-optic lines at power facilities. *Aust. J. Eng. Innov. Technol.*, **8**(4), 346-353. https://doi.org/10.34104/ajeit.026.03460353

Copyright: © The Author(s), 2026. Published by the UniversePG. This is an **Open Access** article, distributed under the terms of the Creative Commons Attribution 4.0 License (http://creativecommons.org/licenses/by/4.0/), which permits unrestricted use, distribution and reproduction in any medium, and provided the original work is properly cited.